BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of the Work : Providing Chain Link fencing and other Works to Indira Canteen opp Chamundeshwari Bus Stop, Doddabommasandra Main Road in Ward No. 10, Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	68.04	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	38.08	Rupees Thirty Eight And Paise Eight Only
2	9.45	Providing and laying in position plain cement concrete of **mix 1:3:6 with OPC cement @ 220 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5449.68	Rupees Five Thousand Four Hundred Forty Nine And Paise Sixty Eight Only
3	207.90	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6**, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4521.96	Rupees Four Thousand Five Hundred Twenty One And Paise Ninety Six Only
4	17.01	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5405.40	Rupees Five Thousand Four Hundred Five And Paise Forty Only
5	37.80	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4 etc complete as per specifications and directions of engineer in charge of the work	Sqm	105.84	Rupees One Hundred Five And Paise Eighty Four Only
6	3.78	Providing and laying in position plain cement concrete of **mix 1:2:4 with OPC cement @ 240 kgs with 40mm** and down size graded granite metal coarse aggregares @ 0.878 cum and fine aggregates @ 0.459 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5876.28	Rupees Five Thousand Eight Hundred Seventy Six And Paise Twenty Eight Only
7	100.80	Supplying and fixing M.S rectangular poles made out of 2 equal angles of 65x656 mm welded together and fixed in CC (1:2:4) with 2 NOS 16 mm dia, M.S hold fast rods each of length 25 cms, including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) etc complete as per specifications and directions of engineer in charge of the work	M	884.52	Rupees Eight Hundred Eighty Four And Paise Fifty Two Only

	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	252.00	Providing and fixing M.S. Block pipe of 38 mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two vertical poles (M.S rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the engineer in charge of work etc, complete including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work	M	349.92	Rupees Three Hundred Forty Nine And Paise Ninety Two Only
9	126.00	Providing chain link fencing 50 mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall bed welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the engineer – in charge of work including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work	Sqm	711.72	Rupees Seven Hundred Eleven And Paise Seventy Two Only
10	6.30	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 gaguge M.S hollow pipe frame work bent to ornimental shape as shown in the drawing and 35 mm x 6 mm and 16 x 16mm squate roads for verticals alternatively spaced at 4 cms c/c in two halves and 40 mm x 6mm M.S Flates for horizontal memeber and at the top cast iron spikes are provided at alternate vertical member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc complete all the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (Shop Paint) etc complete the work includes cost of all materials labour charges, for all items of work, hire chargesfor welding cutting and grainding equipment and electtricity charges with lead and lift loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Sqm	3168.72	Rupees Three Thousand One Hundred Sixty Eight And Paise Seventy Two Only
11	103.50	Grassing with Doobs grass KSRRB M300- 2.1. Grassing with Doobs grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for moving including supplying good earth if needed complete as per specifications. MORTH Specification No. 307 ii) In rows 7.5 cm apart in either direction etc complete as per specifications and directions of engineer in charge of the work	Sqm	97.20	Rupees Ninety Seven And Paise Twenty Only

3/09

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

3/09

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.